





NOTES:

SECTION B-B

- 1. WHERE EXPANSIVE SOILS ARE ENCOUNTERED, AS SET FORTH IN THE STANDARD SPECIFICATIONS, 6" OF IMPORTED SAND, COMPACTED TO 90% RELATIVE COMPACTION SHALL BE PLACED UNDER THE CURB, GUTTER, AND SIDEWALK.
- 2. MATERIAL SHALL BE CLASS "A" CONCRETE IN ACCORDANCEWITH SECTION 7 OF STD. SPECIFICATIONS.
- 3. A 12" WIDE BORDER OF 1/4" X 1/4" WIDE GROOVES 3/4" APART SHALL BE LOCATED ON THE LEVEL SIDEWALK SURFACE AT THE TOP OF THE DRIVEWAY

ALLEY APPROACH
CONSTRUCTION

Date: 10/1/03 STD.
NO.
NO.
P-9